

UTILITY PATENT APPLICATION
INVENTORS: HODSDON & GRENIER
EXPRESS MAIL: ET791107119US

UNITED STATES PATENT AND TRADEMARK OFFICE
WASHINGTON, D.C.

**METHOD AND ADJUSTABLE APPARATUS FOR
MASONRY WALL BRACING**

BACKGROUND OF THE INVENTION.

PREVIOUS FILING INFORMATION.

On September 20, 2003 the United States Patent Office received a copy of - and assigned serial number 60/503,976 to - a Provisional Patent Application (PPA) filed by the same inventors hereof. That PPA is incorporated herein by this reference as though set out here in full. Additionally, the PPA is being supplemented by this Regular Patent Application (RPA). Applicant expressly reserves all rights and privileges flowing from the PPA and its earlier official filing date and contents thereof. This RPA follows, and it is supported by the PPA.

FIELD OF THE INVENTION.

This invention relates to masonry wall bracing and bracing systems for such wall. More specifically, the field of this invention

1 relates to adjustable bracing anchored at a self-supporting base for
2 safely assuring the construction of masonry walls. Additionally the field
3 of this invention relates to a bracing system that sandwiches both sides
4 of a wall under construction by a "connected-through-at-the-base"
5 device which interconnects a pair of bookend right angle braces.

6
7 **EXPLANATION OF TERMS.**

8
9 Our invention involves a pair of right angle adjustable braces
10 abutting both sides of a wall under construction, and offers telescoping
11 adjustments in plumb and height to selected brace members while the
12 brace sets remain positioned against both sides of the wall. The novel
13 system does so without the use of deadmen and all of the attendant
14 disadvantages associated with such deadmen.

15
16 Set out below are brief descriptions of certain relevant terms
17 which further the understanding of the invention. These terms provide
18 a basis for a detailed teaching of the improvements of this invention in
19 the relevant arts. Such terms are not intended to replace the claims
20 but rather serve as helpful guides in understanding our novel
21 improvements in these arts.

22
23 **CONCRETE PILLARS - OR DEADMEN.**

24
25 Standard bracing approaches involve spaced right angle
26 braces - often of wooden timbers - having a vertical member against
27 the wall, an angled member and a horizontal base member running
28 horizontally away from the wall to a gusseted footing plate that is
29 bolted into a concrete pillar set in the ground. These pillars, or so-
30 called "deadmen" each require about a cubic yard or more of concrete
31 per anchoring point.

1
2 For example, the minimum dimension for a deadman as
3 mandated for a 32 foot wall, must be about 3 feet across in both width
4 and depth, and must be set into the ground a depth of about 3 and 1/2
5 feet. (The deadmen for shorter walls may be slightly smaller.) Earth
6 moving equipment, or pick and shovel laborers, are mandatory to
7 install and remove such deadmen. Each one is thus costly to set into
8 place and even more costly to subsequently remove after wall
9 construction is finished. In fact, when short spacing distances are
10 required between bracing, the deadmen often take the form of a solid
11 running concrete trench or bunker. These deadmen requirements pose
12 significant disadvantages of the prior art.
13

14 The invention does not require such deadmen.
15

16 **OUTRIGGER SCREWJACKS.** 17

18 Rather than use deadmen, the invention employs vertical
19 oriented outrigger screwjacks that are adjustably connected at the
20 outermost end of the base, or horizontal, leg of each of the angle
21 braces. Such screwjacks may preferably take the form of a threaded
22 riser formed above a foot plate in contact with the ground. The ground
23 need only have a modicum of levelness and need not be trenched,
24 framed and/or poured as is true for the deadmen requirements of the
25 prior art.
26

27 Extending upward from the screwjack foot plate is a
28 threaded shaft that mates with or passes through a receiving opening
29 at about the outer end of the horizontal leg of the brace. A threaded
30 locking wing is used to secure height adjustments made via this
31 screwjack. Pipe clamps may also be used to hold the adjusted locking

1 wing in place simply as an effort to deter vandalism which is
2 sometimes encountered on construction sites. The outrigger screwjack
3 takes the place of the cumbersome deadmen; and, by comparison, is
4 far more economical, safe and convenient.

5 6 **BASE-LOCATED INTERCONNECTOR.**

7
8 A single connection hole is located through the base of the
9 wall being built to hold a pair of braces together on opposite sides of
10 the wall. This opening - being located at a block course just above the
11 wall's foundation - does not significantly detract visually nor does it
12 weaken the structures as do a series of vertical through openings
13 typical of the prior art. Each brace of the invention, at the right angle
14 location, is fitted with openings that receive a base connector. That
15 connector may be in the form of a long threaded shaft, which shaft is
16 passed through aligned openings in the brace pair and is fitted with
17 nuts for tightening. As the threaded nuts are tightened, the vertical
18 legs of a brace pair are drawn snugly against opposite sides of the
19 wall. They, in turn, hold and support the masonry wall being.

20 21 **TEMPORARY TIE WIRE**

22
23 As a practical matter several courses of blocks will normally
24 have been laid before the inventive brace(s) need be erected on the
25 work site. At a height that may safely and easily be reached by a
26 workman (e.g. standing on a ladder, for example) a short section of tie
27 wire is inserted in one of the higher block courses being laid. This tie
28 wire is vertically in line with the lower connector opening and need only
29 be a short length of wire. Its primary function is simply to receive a few
30 twists by a masonry craftsman around the vertical brace member, in
31 order to temporarily hold the brace upright against the wall. This

temporarily hold by our tie-wire assures that the vertical brace member will remain upright - thus physically freeing a workman so that our connector and leveler means may be appropriately adjusted.

TELESCOPING MEMBERS.

Each vertical and angle (diagonal) brace member of the inventive opposing brace pair may preferably be formed from rugged telescoping steel square tubes that fit within each other. Telescoping of these members achieves length adjustments required for workmen protection as wall height progressively increases. Since the height of each newly laid wall section to be braced may be foreknown, the telescoped tubes are appropriately formed with drilled adjustment holes that are aligned so that they may receive connecting bolts or pins. The length of a brace member can easily be achieved from a scaffold or a ladder, and the two telescoped members (vertical and diagonal) may again be secured together after the required extension to the bracing system has been made. A telescoping bind bolt makes such adjustments easier and more economical.

BACKGROUND - DESCRIPTION OF PRIOR ART

Block walls include internal voids that are filled or "grouted" with wet cement at specified intervals along the wall being constructed. Such walls may soar to various heights in today's building environment. Once the first eight foot height is reached, OSHA mandates - and practical safety requires - that the block wall should be additionally braced. Four feet more of non-grouted masonry wall can be added above that first eight foot limit before more and higher bracing again becomes mandatory.

1 In effect, a block wall goes upward in eight foot increments
2 and common sense safety requires that no more than four feet of non-
3 grouted wall should be added without some additional safety bracing
4 being applied to the construction zone. Construction of such walls also
5 requires scaffolding for the masons. Such scaffolding is stationed at
6 least on one, and often on both sides, of the wall. This invention
7 provides ready scaffolding access for laying up blocks while assuring
8 safety as wet grouting is being poured into the block voids. Indeed, the
9 compact and ease of elevation of the vertical and diagonal members of
10 our inventive brace pair allows workmen to readily accommodate
11 course laying, internal grouting, and custom surface finishing together
12 with an advanced improvement in worker safety as well.

13
14 From a standards point of view, construction of masonry
15 walls places a burden on the mason contractor to support any masonry
16 wall under fabrication that is over eight feet in height. Such walls must
17 be "adequately" braced. Exactly how such bracing is to be performed,
18 however, is left to the discretion of the contractor in accordance with
19 the OSHA standards in effect today. In exercising that discretion for
20 each and every bracing situation, wind factors are of paramount
21 importance. Several of the typical prior art approaches will be
22 discussed below. But first, a brief review of how wind affects the
23 discretionary bracing environment is believed to be warranted.

24
25 Wind speed, with winds varying from calm to gale force
26 constantly buffet a wall being laid up by courses of building blocks.
27 The wind, of course, is never steady; rather, it whips around buildings
28 which may be present and comes in bursts and gusts together with
29 wind variations going from steady to shifting forces.

1 In short, masons must be protected from the cyclic wind
2 loads that are created by the ever changing wind conditions.
3 Otherwise, without adequate bracing, such winds will readily blow
4 down a wall and endanger craftsman in the masonry trades. It is not
5 unknown for workmen to be killed or seriously injured when walls are
6 not adequately braced.

7
8 Any wall that has not yet been "cured" sufficiently is at risk
9 unless it is adequately and safely braced. Indeed, such wall destruction
10 happens in spite of the various prior art attempts to use strengthening
11 members and prior art bracing sections as are commonly found in wall
12 construction.

13
14 A block wall under construction is looked upon, for
15 evaluation purposes, as comparable to the sail of a water craft. The
16 well known Beaufort Wind Scale is deemed applicable and the various
17 marine Beaufort numbers are deemed to apply to the Masonry
18 Industry. While originally applicable only to wind conditions at sea, that
19 Beaufort scale has been modernized and modified to take into
20 accounts land affects.

21
22 The modified table below sets forth some of the relevant
23 wind factors which must be taken into consideration.

24
25 **TABLE**

26

<u>Beaufort No.</u>	<u>Wind speed</u>	<u>Effects on Land</u>
27 0	Calm	Smoke rises vertically.
28 1	1 - 3	Rising smoke drifts, weather
29		vane is inactive.
30		

1	2	4 - 7	Light Breezes: Leaves rustle, can
2			feel wind on your face.
3	3	8 - 12	Gentle Breezes: Leaves and
4			twigs move around.
5	4	13 - 18	Moderate Breezes: Moves thin
6			branches.
7	5	19 - 24	Fresh Breezes: Trees sway.
8	6	25 - 31	Strong Breezes: Large tree
9			branches move.
10	7	32 - 38	Moderate Gales: Large trees
11			sway.
12	8	39 - 46	Fresh Gales: Twigs and
13			Branches are broken from trees.

14

15 Three common prior art methods are employed to try to

16 safely brace walls in view of the varying wind conditions set out above.

17 In the first method, wooden diagonally placed timbers were positioned

18 at one end against the wall and such timbers at the other remote end

19 are tied to a deadmen, or to posts driven in the ground. Vertical,

20 horizontal and diagonal timbers are often nailed or screwed together in

21 a rather helter smelter wooden jumble.

22

23 This wooden bracing method may also include wooden

24 struts connected at the midpoint of the diagonal brace, which struts run

25 toward the base of the wall being built. This wooden bracing is not at

26 all acceptable. Such bracing is subject to cyclic loading from the wind

27 forces and tends to become seriously weakened. Indeed, it is felt by

28 some that this jumbled wooden approach of the prior art creates other

29 serious safety hazards.

30

1 some that this jumbled wooden approach of the prior art creates other
2 serious safety hazards.

3
4 In short summary, this wooden timber jumble itself poses
5 safety hazards such as sliding upward as the walls tend to move to
6 move. Actual wooden brace sliding along the surface of a leaning wall
7 may happen and failures result. Additionally, broken planks and
8 splintered wood abounds. Such wooden bracing is both an attractive
9 nuisance, dangerous in operation and "free" lumber is available for
10 unauthorized taking.

11
12 Another typical prior art approach employs a vertical metal
13 beam secured to the face of the wall and held in place by a series of
14 bolts passing through the masonry blocks and the vertical beam itself.
15 A Brace-rite system marketed under a Duro-o-wall trademark is one
16 such prior art type, and it is described in detail in the Technical Bulletin
17 99-2 Unit Masonry manual incorporated herein as though set forth in
18 full at this point.

19
20 The above-mentioned Brace-Rite type includes a bolted-
21 through plate which causes serious wall damage and weakens the
22 structural integrity of the wall. Moreover, it mars the outer masonry
23 block surface - especially troublesome and costly when a decorative
24 exterior wall finish is sought. This is a costly approach both to install
25 and then later to remove. In particular, it creates increased finishing
26 costs needed for removal and the subsequent repairs needed to cover
27 the bolted through hole locations. Moreover, the system requires extra
28 costs and suffers the numerous drawbacks of deadmen - which
29 drawbacks are essentially eliminated by our invention.

1 Another prior art approach employs cables and turnbuckles
2 anchored between deadmen and cable eyes secured at openings
3 through the wall. Again the wall is damaged and the points of
4 connection - although unwieldy - may not provide efficient support.
5 These and other drawbacks of the prior art are set forth in various
6 available publications including "Masonry Bracing" published by the
7 Masonry Contractors Association - a July 2001 is of particular interest
8 and it is incorporated herein as though set forth in full at this point.

9
10 The various shortcomings of these and other prior art
11 approaches are overcome by our invention. Indeed, costing out a
12 masonry job based upon prior art supporting techniques is several
13 times higher than when our new and novel bracing system is
14 employed. Additionally, and perhaps most important, is that worker
15 deaths or injuries resulting from inadequate prior art bracing will be
16 markedly reduced.

17 18 **SUMMARY OF THE INVENTION**

19
20 In the invention, each right angle brace includes a horizontal,
21 vertical and diagonal member preferably fashioned from rigid steel
22 tubing that may be interconnected by bolts and/or connecting pins into
23 a stiff rigid right angle brace. Suitable coupling at the corners of the
24 brace assures easy folding of these members so that the brace
25 members are readily portable in sections by a single workman.

26
27 For example, the inner telescoping members may be
28 separated from the receiving outer triangular telescope brace sections
29 in order to provide for less weight and manual transport considerations.
30 Once inserted, however, such telescoping members are bolted, pinned
31 or otherwise suitably fastened together for on site bracing. In

1 contradistinction to the prior art, the inventive right-angle brace sets
2 are located, adjusted and compressively interconnected back-to-back
3 on opposite sides of a wall under construction. The connector means is
4 locked within the opening and such means may take any one of many
5 different forms. In our embodiment(s) the connector/adjustment means
6 may be spring loaded, winch-like or more simply a threaded steel shaft
7 for adjustably connecting, leveling and interconnecting the braces of a
8 back-to-back pair.

9
10 A connector is passed through a hole in the base of the wall
11 and through aligned mating holes in the vertical riser at the right angle
12 corner of each opposing brace of a support set. Such a threaded shaft
13 may simply be secured by mating threaded nuts at the outside 90°
14 corners of the two opposed braces. Manual tightening of such nuts
15 (plus outrigger adjustment) brings the brace sets together in such a
16 manner that the vertical risers of both of the brace sets are vertically
17 aligned against the wall under construction.

18
19 Vertical oriented screwjacks located in receiving openings at
20 the remote end of the horizontal outrigger, adjust for any unevenness
21 at the construction site; and, when raised and lowered, assures that
22 the vertical riser of each right angle brace set will be a flush fit securely
23 against the masonry wall being braced. A flush fit by the vertical riser
24 brace member assures workmen safety in a wall braced by our
25 system.

26
27 Both the vertical riser and the diagonal legs of our novel right
28 angle brace sets include telescoping rigid struts which allow for height
29 adjustments to such bracing as is periodically mandated by increases
30 in height during wall construction. A simple and novel twist wire is
31 employed as a method of assembling and securing the right angle

1 braces to the wall. This feature of the invention is free of bolts and
2 holes of the prior art that mar or weaken the visible surface of a wall.
3 No deadmen, posts or land anchors of any type are required for the
4 interconnected opposed brace sets equipped with outrigger screwjacks
5 in accordance with the principles of this invention.

6
7 The novel features of the disclosed invention provide many
8 benefits. These benefits are achieved by an invention that:

- 9
- 10 • Meets or exceeds OSHA requirements.
 - 11 • Is readily useable on small to large projects.
 - 12 • Provides vertical adjustability in a simple and ready manner.
 - 13 • Is easily transportable.
 - 14 • Is easy to set up and/or breakdown thereby minimizing man
15 hours and associated costs required for wall construction.
 - 16 • Requires minimum material handling time for setup or
17 removal.
 - 18 • Involves minimum wall penetration to reduce man hours and
19 man-lift time for setup and/or removal.
 - 20 • Eliminates the use of deadmen, land anchors, anchor posts
21 and the like together with their attendant disadvantages and
22 costly installation and removal.

23
24 **DRAWINGS**

25
26 Figure 1 is a perspective view of one embodiment of a wall
27 brace constructed in accordance with the invention;

28
29 Figure 2 shows an end view of a pair of supports of Figure 1
30 placed on opposite sides of a wall;
31

1 Figure 3 depicts workmen rotating a brace set into an upright
2 position for bracing a block wall in accordance with the method steps
3 of this invention;

4
5 Figure 4 shows a connector coupling a pair of opposed
6 brace supports through an opening in a wall being fabricated;

7
8 Figure 5 includes is an enlarged view of an outrigger
9 screwjack of Figure 1; and

10
11 Figure 6 depicts the telescoping feature for the brace sets of
12 this invention.

13
14 **DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENT**

15
16 Figures 1 and 2 are views helpful in fully understanding our
17 bracing invention. Each brace 10 as shown is a unitary right angle
18 brace, preferably formed from sturdy square tube steel members,
19 which members are bolted, welded or otherwise assembled into a
20 unitary right angle brace structure 10. A brace 10 is moved on site in
21 separated member fashion and may be assembled while leaning on
22 the ground. And then, the assembled frames is manually rotated (See
23 Fig. 3) and held upright level and flush as will become clearer from the
24 additional description of the invention.

25
26 While primarily intended to be employed in opposing pairs
27 (See Figure 2) our invention may, in a particular case, consist of a
28 single right angle brace 10 held flush against a wall by adjustable
29 connecting and leveling means (80 and 55, Figure 1, respectively).
30 Most often, however, our preferred embodiment is as shown in Figure
31 2 depicting a pair of braces 10a and 10b, in back-to-back upright

1 position aligned and held flush and plumb along a common vertical on
2 opposite sides of a wall under construction.

3
4 A wall 11, as well known, is normally "laid up" to various
5 heights by workers placing standard concrete block, layer upon layer,
6 extending upward from a wall's base foundation. Each brace 10 of
7 Figure 1 has a horizontal member 30, vertical member 40 and an
8 angled, or diagonal, member 50. These members may either be single
9 non-telescoped pieces or they may be telescoped together to
10 accommodate differing wall heights and size requirements.

11
12 Comparison of the braces of Figure 1 shows that the
13 telescoped members 40 and 50 of the right hand brace have been
14 elevated in order to accommodate and offer support for the increased
15 height of wall 11. Figure 1 also reveals that the telescoped members
16 40 and 50 of the left hand brace have both been extended as
17 necessary to support the higher height of wall 10. Workmen on
18 scaffolding (not shown, but provided for by the invention's close fit to
19 the wall 11) simply lift the vertical and diagonal telescoping members
20 40, 50 as wall 11 increases in height.

21
22 In the method of practicing this invention hole 81 is either left
23 or bored at about (or slightly above) the first block course at base 12 of
24 a wall 11 to be fabricated. The steps in our invention will now be
25 described in more detail.

26
27 It should be understood that the foundation 12 for a block
28 wall 11 is often wider than the width of the individual blocks 13 which
29 make up wall 11. Figure 4 is an enlarged partial view at the base of
30 the wall 11, which view shows a connector opening 81 for a pair of
31 opposed brace sets on opposite sides of a wall 11. As shown, the

1 innermost edge 10e of each brace set 10 of this invention may rest on
2 the foundational overhang, while being interconnected to each other by
3 threaded shaft 70 through opening 81 in the block wall 11. Rotation of
4 the loosely connected brace set 10 will allow such a set to be placed
5 on that edge 10e where it may then be secured as described further
6 hereinafter.

7
8 Please note that the inner and outer telescoping members
9 (Figure 6) may be separated. That is to say, that the outer telescope
10 housing 50o of the diagonal 50 may be slid away from the inner
11 telescope 50i. The same is true for the vertical members 40o and 40i.
12 Thus, these brace members may all be separable in order to lighten
13 the portability load for a workman.

14
15 At first the individual members - singularly or in partially
16 folded form - are carried to a site and are often there assembled and
17 leaned on the ground loosely connected to each other through a
18 connecting means - such as threaded shaft 70 - at the base connector
19 opening 81. Such members may then be pinned, bolted or otherwise
20 fastened together to form a rigid unitary right angle brace 10 of the
21 invention. Figure 3 depicts a workman in the process of raising an
22 assembled set 10, previously leaning on the ground, to an upright
23 position.

24
25 Method steps, in summary, include tilting the assembled
26 brace set 10 upright - the process being partially shown by Figure 3.
27 Then, the upright set is temporarily held in place via a tie wire 60.
28 Then connector 80 and screwjack 55, Figure 1, are adjusted and
29 tightened so that the upright brace set will provide brace support to one
30 or both sides of a wall 11.

1 Getting the rigid assembled brace set 10 upright and plumb
2 involves rotation about an adjustable connecting means 80, leveling
3 the horizontal and vertical members to their desired positions by height
4 adjustments at element 55, and then maintaining same free of further
5 manual assistance by a tie wire 60 as described in more detail below.

6
7 As a practical matter several courses of blocks will have
8 already been laid on the wall before the bracing system of our
9 invention need be erected for support of the wall. Above eye height, at
10 a position that may easily be reached by a workman on a ladder, a
11 short section of tie wire 60, Figure 1, is inserted in a selected one of
12 the block courses being laid. That wire 60 need only be a short length
13 of wire, perhaps about haywire thickness. Preferably, although it need
14 not be mandatory, this tie wire 60 will be wrapped around an internal
15 vertical riser of reinforcing rod of the type commonly used in block wall
16 construction.

17
18 The primary function of this tie wire 60 is simply to allow a
19 workman to place a few twists about the vertical brace member 40 and
20 hold that member 40 - and, thus the entire rigid brace 10 - upright in
21 position against the wall 11. Twisted tie wire 60 temporarily holds the
22 vertical upright in its proper place, and frees the workman from any
23 further manual attention in holding brace 10 in place.

24
25 This invention, Figure 5, provides a pair of outrigger
26 screwjacks 55 (one screwjack for each brace set) to be adjusted in
27 height such that the horizontal member(s) 30 are essentially level with
28 the ground. As noted above in connection with the discussion of
29 deadmen, the earth around construction sites is often neither level nor
30 in good repair. The outrigger screwjacks 55 of our invention greatly
31 alleviate such surface problems inasmuch as the screwjacks 55 of our

1 invention include a foot plate 52 which readily accommodates uneven
2 ground.

3
4 The amount of upward force that must be applied by
5 screwjack 55 need only overcome the weight of right angle brace 10
6 and provide adequate support for the loading vectors expected for
7 wind loads. This weight is not very great, and the wind chart set forth
8 earlier will readily yield the load vectors to be accommodated while the
9 brace is being held upright by tie wire 60, connector 80 and leveler 55.
10 Accordingly, a simple threaded screwjack riser shaft 54, Figure 1, of
11 about an inch or so in diameter has proven adequate to satisfy these
12 purposes of our invention.

13
14 Riser shaft 54, Fig. 5, slips within a slightly oversized,
15 circular receiving collar 57 welded to horizontal member 30. Leveling
16 is accomplished by advancing or retracting wingnut 58 that is matingly
17 threaded to travel upwards or down on riser shaft 54. Cap 59 covers
18 the exposed end of riser 54 for safety purposes.

19
20 Other similar leveling devices, such as manual or hydraulic
21 jacks, or any one of a wide variety of known leveling devices would
22 equally suffice in place of screwjack 55; and, such devices remain
23 within the novel features of our invention. Masonry tradesmen in
24 general are familiar with such screwjack leveling devices as they find
25 extensive use on scaffolding. Thus, in our preferred embodiment we
26 have shown a screwjack 55 rather than some other suitable alternative
27 such as those mentioned above.

28
29 Briefly returning again to Figures 4 and 5, please note that
30 vertical member 40 has freedom of rotational movement into and away
31 from the wall 11 by a nut/bolt fastener 97 seated within a pair of

1 triangularly-shaped strengthening flanges 99. This fastener 97 may, of
2 course, also take the form of a pin passing through openings in the
3 flange 99 and held there by any well known securing device, such as a
4 pull ring or clip (not shown, but understood in this art).

5
6 For leveling purposes at Figure 5, a workman simply spins
7 (advances and/or lowers) the wing tightener 58 on screwjack shaft 54
8 until the horizontal brace member 30 is essentially level and the
9 vertical member 40 is flush against wall 11. The workman then finishes
10 securing connector 80 so that the vertical members 40 of our right
11 angle brace invention 10 are snug and flush against the masonry wall
12 11. Adjusting connector 80 slightly - plus some final adjustments to
13 screwjack 55 - readily brings the vertical member(s) of our bracing
14 system invention 10 into a slight compressive condition against the
15 surface of wall 11. If previously loosened, then bolt/nut 97 must also
16 be tightened to bring the brace into a desired state of rigidity for
17 maximum effective support.

18
19 At the innermost end, Figure 4, of the horizontal member 30
20 we have elected to weld a pair of spaced apart flanges 99 to the
21 horizontal member 30. Obviously, however, member 30 may be bolted
22 or otherwise suitably fastened to the spaced apart flange pair 99. We
23 outfit the other end of that horizontal member 30 with a vertical
24 receiving collar 57, Figure 5. Receiving collar 57 has an inside
25 diameter that readily accepts an upright threaded shaft 54 of screwjack
26 55.

27
28 Often times work sites face vandalism particularly by
29 juveniles. It would, to idle juveniles, be considered great "fun" to spin
30 the wing nut 58 down on post 54. A simple coupling like a radiator
31 clamp (not shown) may be fastened below wing tightener 58 to deter

1 such vandalism inasmuch as the vandals may not have screwdrivers
2 with them during their "playful" excursion unto the construction site.

3
4 Figure 6 depicts that inner diagonal member 50i is slidably
5 seated within outer diagonal member 50o. With binding bolt 90
6 loosened, the inner member 50i may be slid out axially from the outer
7 member 50o. Bolt 90 may then be made secure and any conventional
8 fastener, 94 such as a cross pin with a ring clip, or a nut and bolt
9 combination may be placed through the mating holes located in both
10 telescoping members 50i and 50o.

11
12 Binding bolt 90 assists in the above-described telescoping
13 feature. That bolt 90 may be loosened and tightened as adjustments
14 are made during the telescoping operation described herein.
15 Additional erection assistance is provided by a lifting pole 110 that has
16 a saddle 111 at its upper end. Saddle 111 is selected with a width and
17 depth that will readily allow the diagonal member 40 to fit within the
18 saddle 111. As workmen are tilting the brace upright, Figure 3, the
19 lifting pole 110 allows ease of moving the assembled brace into an
20 upright position.

21
22 Also note that the top of the inner telescoping member 40i
23 has a cover plate 96 that may be separate from - or attached to and
24 made a part of - a wall spacer flange 98. The thickness of the spacer
25 flange 98 compensates for the small amount of separation between the
26 surfaces of the inner and outer members 50i and 50o, respectively.
27 Spacer flange 98 fits against the wall, and although there may be a
28 small length of the vertical member 40i that is not actually flush against
29 the wall, the use of flush in this inventive system takes into account
30 that small degree of separation which does not detract from the brace
31 support features of this invention.

1
2 As workmen do masonry work on the scaffolding (not
3 shown) loose wet mortar drops down. Also, as well known, such wet
4 mortar is "pointed", or scraped away at the block seams, during the
5 block laying and joint finishing process for wall 11. The cover cap 97
6 on the top of the vertical member keeps the dropping mortar from filling
7 the vertical tube sections and interfering with the expected and desired
8 sliding freedom between the telescoping members 40i and 40o.

9
10 Since the height of each newly laid wall section to be braced
11 is foreknown, the telescoped tubes may be appropriately formed with
12 drilled adjustment holes that are aligned so that they may receive
13 connecting bolts or pins. Alternately, of course, a series of spaced
14 length adjustment holes may be placed in each telescoping member
15 pair. The length of a brace member can easily be adjusted as
16 necessary, and the telescoped members (vertical and diagonal) may
17 again be secured together after the required extension to the bracing
18 system has been made.

19
20 The method and apparatus of this invention allows
21 scaffolding of conventional type (not shown) to be erected above our
22 inventive bracing system without interfering with the brace sets per se.
23 Our invention increases, in rather dramatic fashion, masonry craftsmen
24 safety while working on block wall 10.

25
26 While my invention has been described with reference to
27 particular examples of some preferred embodiments, it is my intention
28 to cover all modifications and equivalents within the scope of the
29 following claims. It is therefore requested that the following claims,
30 which define my invention, be given a liberal interpretation
31 commensurate with my contribution to the relevant technology.